

Stage Four – Configure Local Router Redundancy (VRR)

To complete this portion of the project you will need to be able to accomplish the following tasks:

- Configure all four switches in the POD to provide local network access to all POD members
- Each POD member must configure their Linux Router to provide External /Internet access for themselves and other members of the POD
- Configure all devices to provide route and device redundancy in the event of a failure (cables and interface failures, device and power failures, etc.)

Apply the new configurations

- Using the scripts provided, reconfigure all networking devices (Aruba, Linux)
- Notice the slight differences in the FRRconfig files provided for this stage. Be prepared to explain them.
- Edit the provided scripts to use the same Vlan and IP scheme **that you created in Stage 2.**

Final Testing/Visual Inspection

- Once you have the new topology configured, test all of your services as we did in Stage 2 and Stage 3
- Using the command **show vrrp** identify the MASTER switch. Go to the back room and unplug the MASTER switch
- Using the command **show vrrp** identify the MASTER switch (It should have changed to the BACKUP switch.) Test all services as we did in Stage 2 and Stage 3
- Restore power to the switch and restore your configuration to the switch.
- Using the command **show vrrp** identify the MASTER switch (It should have changed back to the original switch.)

Documentation Submission

- Include the following screenshots:
 - The output of **sh vrr** on both switches **BEFORE and AFTER** the power cut.
(4 Screenshots)
- The scripts you/your group used to configure **all** Aruba switches in your POD and your Linux router configuration (**FRR**)